

QUOTATION NOTICE

NCRMI invites competitive quotations from interested parties for the work related to the setting up of Meteorological Observatory at NCRMI Campus. The details of work enclosed with.

The quotations shall reach Director, NCRMI on or before 08.02.2018 at 3.00 pm. Quotations will be opened on the same day at 03.30 pm in the presence of the quotationers present. The Director, NCRMI reserves the right to accept or reject any or all the quotations without assigning any reason whatsoever.



DIRECTOR
NCRMI

SL No.	Particulars	Quantity	Unit	Rate quoted by the contractor	Amount
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	84	m ²		
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan)	2.98	m ³		
3	1 Cement : 2 coarse sand : 4 (graded stone aggregate 20 mm nominal size)	1.01	m ³		
4	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:Cement Mortar 1:6 (1 cement : 6 coarse sand).	3.84	m ³		
5	12 mm cement plaster of mix : 1 : 4 (1 cement: 4 fine sand) for plastering	18.53	m ²		