

**QUOTATION NOTICE**

NCRMI invites competitive quotations from interested parties for the work related to the Demonstration project – “Coir Geocell- A sustainable and Environment friendly product for slope land stabilisation and cultivation” The details of work are enclosed.

The quotations shall reach Director, NCRMI on or before 16.09.2021 at 3.00 pm. Quotations will be opened on the same day at 03.30 pm in the presence of the quotationers if any present. The Director, NCRMI reserves the right to accept or reject any or all the quotations without assigning any reason whatsoever.

Sd/-

Director  
NCRMI

| Sl. No. | Description of work   | Quantity | Unit           | Rate quoted by the contractor |
|---------|---|----------|----------------|-------------------------------|
| 1       | Clearing the plot including uprooting of rank vegetation, grass, removal of rubbish up to a distance of 50 m outside the periphery of the area cleared including surrounding the project site   | 491.4    | m <sup>2</sup> |                               |
| 2       | Earth filling with topsoil (including levelling of the slope area at a perfect slope of 38%): -using available excavated earth (excluding rock)in project plot, layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m. | 18.75    | m <sup>3</sup> |                               |
| 3       | Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth up to 50 m and lift up to 1.5 m  | 159.86   | m <sup>2</sup> |                               |
| 4       | Supply of 8mm dia 50cm long MS rod : 1m of 8mm diams bar=.395kg   | 224      | nos.           |                               |

|    |   |                |                  |  |
|----|---|----------------|------------------|--|
| 5  | (a) Supply, cutting& fixing of bamboo strips for geocell(size 50x2.5cm) including labour charge for cutting of bamboo strips<br><br>(b) Supply, cutting& fixing of bamboo strips for geotextile (size 30x2.5cm). including labour charge for cutting of bamboo strips | 300<br><br>200 | nos.<br><br>nos. |  |
| 6  | Plastering the damaged portion of sedimentation tank & replacing brass taps(3nos.) Fixing of drainage taps in siltation tank(3nos.)   | LS             |                  |  |
| 7  | (a) Supply of 22 gauge corrugated sheet of size 3.05 x 0.45   | 10             | nos.             |  |
|    | (b) Labour charge for fixing corrugated sheet in either side of drain ditch using MS rod.   | LS             |                  |  |
| 8  | Painting on drainage sheets, collection drum & accessories and Painting on the board  | 185.3          | m <sup>2</sup>   |  |
| 9  | Filling of available earth in the geocell   | 18.75          | m <sup>3</sup>   |  |
| 10 | Cutting & laying of geotextile<br><br>(a) cutting of geotextile   | 150            | m <sup>2</sup>   |  |
|    | (b) laying of geotextile  | 150            | m <sup>2</sup>   |  |
|    | (c) laying of geocell   | 125            | m <sup>2</sup>   |  |